






28 Toronto 3x3

ID	Name	Height	Width	Length	Qty	3D Front Axonometry	
FBE-1	Floor bearer	28	60	2800	6		
A01	Wall A	135	28	790	14		
A02	Wall A	135	28	790	14		
A03	Wall A	135	28	2990	1		
A04	Wall A	135	28	740	3		
A05	Wall A	135	28	740	3		
A06	Wall A	135	28	3200	1		
B01	Wall B	135	28	2990	3		
B01	Wall B	135	28	2990	11		
B02	Wall B	135	28	3200	1		
C01	Wall C	135	28	2990	1		
C02	Wall C	135	28	2990	14		
C03	Wall C	135	28	2990	1		
C04	Wall C	135	28	2508	1		
C05	Wall C	135	28	1790	1		
C06	Wall C	135	28	1072	1		
C07	Wall C	135	28	354	1		
D02	Wall D	135	28	2990	1		
D03	Wall D	135	28	2990	14		
D04	Wall D	135	28	2990	1		
D05	Wall D	135	28	2508	1		

D06	Wall D	135	28	1790	1		
D07	Wall D	135	28	1072	1		
D08	Wall D	135	28	354	1		
EXTRA	Wall Extra	135	28	2990	1		
PR-1	Purlin	140	44	3200	3		
RB-1	Roof board	19	87/110/135	3358	38/30/25		
FB-1	Floor board	19	87/110/135	2739	33/26/21		
TRIM	Trim	40	19		12 m'		
WBA	Windboard A	90	19	3596	2		
WBB	Windboard B	70	19	3200	2		
WBC	Windboard C	19	40	3596	2		
WBD	Windboard D	25	30	3200	2		
STRM-BR	Storm braces	47	28	1980	4		
Instalaltion kit for assembly							
N01	Nail	---	2,5	40	450 (50+2*200)		
S-01	Screw	---	3	40	50		
S-03	Screw	---	5	100	10		
S-04	Screw	---	5	120	15 (5+10)		
SB	Washer	---	M10	---	8		
	Screw	---	8	50	8		